

Reference times for warranty tasks

Axles:

Disc DOKTX1 09010 4345H1 | GAKTX1 09010 4218 F

	No.	Component	Work step	Reference [min]	Upstream tasks	Work time, complete [min]
General		Vehicle	Set-up time, complete	30		
	2	Wheel	Dismounting and	10		
		Air gap, brake	Checking and adjusting	6	2	16
	4	EBS/ ABS brake system	Reading out the error	30		
Disc	5	Brake calliper, 1 pc.	Overall check	7	2.8	29
	6	ABS wheel sensor	Removing and installing	4		
	7	Diaphragm brake cylinder	Removing and installing	15	2	25
	8	Brake lining	Removing and installing	12	2.3	28
	9	Brake calliper	Removing and installing	25	2,3,7,8	68
	10	Wheel flange, complete	Removing and installing	12	2,3,7,8,9	80
	11	Brake disc	Removing and installing	25	2,3,7,9,10	93
	12	Wheel bearing unit	Removing and installing	20	2,3,6,7,8,9,10	104
	13	Wheel studs per wheel	Removing and installing	20	2	30
	14	Thrust piece with bellows and inner	Removing,	25	2,3,8	53
		seal	installing and			
	15	Guide bushing (floating bearing, DU	Removing and installing	15	2,3,7,8,9	83
		Thrust bearing guide bushing	Removing and installing	20	2,3,7,8,9	88
	17	Bellows, inner	Removing and installing	9	2,3,7,8,9	77
Drum	5	Brake cylinder	Removing and installing	15		
	6	Hub unit with brake drum	Removing and installing	10	2	20
	7	Brake drum	Removing and installing	6	2.6	20
	8	Brake shoes	Removing and installing	4	2,6,7	24
	9	Outer, inner wheel bearing, seal	Removing and installing	20	6	30
	10	Slack adjuster	Removing and installing	10		
	11	S camshaft, camshaft bearing,	Removing and installing	20	6,7,8,10	46
		camshaft bushing	<u> </u>			
		Dust cover	Removing and installing	8		
General		Toe measurement, 2 axles, complete		65		
		Toe measurement, 3 axles, complete	 	80		
		Axle, complete incl. toe	Removing and installing	195		
		Air bellows (1 pc.)	Removing and installing	20		
		Shock absorber (1 pc.)	Removing and installing	15	04.00.04	
	23	Spring (1 pc.), incl.	Removing and installing	95	21, 22, 24	
		secondary tasks, without	5			
	24	Clamp plate and U-bolt, 1 side,	Removing and installing	50		
		without secondary tasks				
	25	Air suspension bracket with	Removing and installing	195	22	
		support incl. all secondary tasks				
	27	Axle lift	Removing and installing	20		

All time specifications are in minutes.

The times specified in the Work time column refer to $\underline{\text{one wheel side}}$ without set-up time.

